Estimate for the approximate quantity for constructing Sylk pattern drains in Chikballapur Town for the year 1939-40.

Item No.	Description of work	Unit	Quantity
I	Constructing sylk pattern drains with new burnt stone slabs of 3″ thick in surki concrete bed of 3″ thick and forming a central channel portion with cement concrete 1 : 2 : 4 for sides and bottom over 1½″ thick cement concrete bed and surface plastered over with ½″ thick cement mortar including earthwork, etc., complete as per design—		
1	6″(3) sylk pattern drain	R.ft.	700
2	6″(2) do	,,	260
3	3″ do	,,	4,420
4	Constructing "L" pattern drains with new slabs of 3″ thick in surki concrete bed of 9″×4½″ and rounding of the centre portion with cement concrete and cement mortar plaster, etc., complete as per design	,,	670
5	Improving the existing box-drain by raising the bed with 3″ thick surki concrete and putting 1½″ thick cement concrete bed and forming the invert and plastering ½″ thick cement mortar including cement mortar pointing to the sidewalls, etc., complete as per design	,,	600
	Rates to the following items of works also to be quoted.		
6	Constructing sylk pattern drain of 3″ section with available slabs on 3″ thick surki concrete bed and forming an invert with cement concrete 1 : 2 : 4 over 1½″ thick bed of cement concrete including the dismantling of old drain splitting dressing conveying fixing and the surface plastered over with ½″ thick cement mortar, etc., complete as per design ..	R.ft.	..
7	New burnt stone in clay	C.ft.	..
8	Providing and fixing 6″ thick burnt stone slabs with rough dress ..	Sq.ft.	..
9	Cement mortar pointing	Sqr.	..
10	Do plaster ½″ thick (1 : 3)	,,	..
11	New size stone in mortar	C.ft.	..

K. S. HUTCHA RAO
Sanitary Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Notification No. '9 *of* 1939-40, *dated* 11*th December* 1939.

1. Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer, Bangalore, up to 2 P.M. on 29th December 1939 for sinking a well on the Cattle Breeding Station, Ajjampur, and improving the well on the Cattle Breeding Sub-Station, Basur, Kadur Taluk.

2. The approximate estimate of quantities for the above works are given below.

3. The quantities are not guaranteed. The works should be completed within one month from the date of acceptance of tender.

4. Earnest money of Rs. 70 and Rs. 30 in cash should be remitted under Revenue Deposit in the Kadur Taluk Treasury, or State Huzur Treasury, Bangalore, with a chellan duly filled in by the tenderer. The tenders should be superscribed 'Sinking a well on the Cattle Breeding Station, Ajjampur' or 'Improving the well on the Basur Sub-Station.' The tenders will be opened at 2-30 P.M. on 29th December 1939.

5. Subject to the formal sanction of the Director of Agriculture, the acceptance of tenders rest with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

6. Within a week of the acceptance of the tender, the successful tenderers will be required to furnish a cash security of 5 per cent of the value of the work and to execute the usual contract bond in default of which their tenders will be considered as cancelled and the security deposits forfeited.

7. The name of the successful competitor whose tender has been accepted will be notified in due course.

8. After acceptance of the successful tender, the earnest money deposited on therefused tenders will be arranged to be returned to the parties.

9. Rates over tendered rates will on account be enhanced.

10. Quotations must be written both in words and figures.

11. The measurements checked by the Agricultural Engineer will have to be accepted as final.

I. Statement showing the approximate quantities of work for sinking a well on the Cattle Breeding Station, Ajjampur.

No.	Description of work	Per	Quantity
1	Excavation in loose soil, 1st mettoo	C.yd.	137
2	Do Semi hard soil 2nd mettoo	,,	137
3	Do hard soil 3rd mettoo	,,	137
4	Do soft rock 4th mettoo	,,	109
5	Do semi-hard rock 5th mettoo	,,	109
6	Steining with dry stone 1′ to 1½′ packing with jelly behind the stone work with bond slabs for every 5 feet in each course in 1st mettoo	,,	28
7	Do do do 2nd mettoo	,,	28
8	Do do do 3rd mettoo	,,	28
9	Baling water	L S.	
10	Pumpside excavation	C.yd.	22
11	Dry stone revetment	,,	8

II. Statement showing the approximate quantities of work for improving the well on the Basur Sub-Station, Kadur Taluk.

1	Earthwork excavation widening the well, 1st mettoo	C.yd.	30
2	Do do do 2nd mettoo	,,	30
3	Do do do 3rd mettoo	,,	30
4	Do do do 4th mettoo	,,	30
5	Steining with dry stone with packing of jelly behind the stone work 1st mettoo	,,	12
6	Do do do do 2nd mettoo ..	,,	12
7	Do do do do 3rd mettoo ..	,,	12
8	Do do do do 4th mettoo ..	,,	12
9	Bond slabs 6″ thick	S.ft.	393

M. G. SINGARACHAR,
Agricultural Engineer.

BANGALORE CENTRAL JAIL.

Notification dated 11th December 1939.

Notice is hereby given that sealed tenders in triplicate will be received up to 10 A.M., but not after, on Wednesday the 27th December 1939, by the Superintendent of the Bangalore Central Jail, for the supply of Vegetables for the consumption of prisoners confined in the Jail, during the Calendar year 1940.

2. Tenders will be superscribed as follows :—

"Tenders for the supply of vegetables for the Bangalore Central Jail."

3. No tenders will be received unless accompanied by a deposit of Rs. 50 either in cash or currency notes.

4. Tenders will be opened by the Superintendent of the Bangalore Central Jail, at his office on the date and the hour abovementioned, in the presence of such tenderers as may choose to attend.

5. All tenders must specify in words and figures the rates at which vegetables will be supplied in pound weight per rupee. No separate rates for each kind of vegetables need be quoted, but rates should be specified for greens on one side and solid vegetables on the other.

6. The probable quantity of vegetables required will be from 300 to 350 lbs. daily and it must be supplied by 9 A.M. every day, but the quantity cannot be guaranteed. The contractor will be required to supply vegetables daily except on those days when the supply of vegetables grown in the Jail garden is sufficient for requirement.

7. Only good and succulent vegetables after inspection and approval by the Superintendent or the Medical Officer of the Jail will be accepted. Vegetables rejected should be replaced within an hour of rejection and the decision of the Superintendent shall be final in all matters concerning the quality of vegetables.